

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) *H.B.L.G.*

Official Number. <i>118,137</i>	Name of Ship. <i>"Saint Irene"</i>	No., Date, and Port of Registry. <i>9/1902 Liverpool</i>
------------------------------------	---------------------------------------	---

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built. <i>British</i>	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled. <i>Steam screw</i>	Where Built. <i>Dumbarton</i>	When Built. <i>1902</i>	Name and Address of Builders. <i>Archd. McMillan & Son Ltd. Dumbarton.</i>
---	---	----------------------------------	----------------------------	---

Number of Decks ... <i>One</i>	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet. <i>345</i>	Tenths. <i>3</i>
Number of Masts ... <i>Two</i>	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	<i>345</i>	-
Rigged ... <i>Schooner</i>	Main breadth to outside of plank ...	<i>47</i>	<i>5</i>
Stern ... <i>Elliptical</i>	Depth in hold from tonnage deck to ceiling at midships ...	<i>22</i>	<i>2</i>
Build ... <i>Blucher</i>	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	-	-
Galleries ... <i>None</i>	Depth from top of beam amidships to top of keel ...	<i>24</i>	<i>75</i>
Head ... <i>None</i>	Depth from top of deck at side amidships to bottom of keel ...	<i>24</i>	<i>95</i>
Framework and description of vessel ... <i>Steel</i>	Round of beam ...	-	<i>96</i>
Number of Bulkheads ... <i>Six</i>	Length of engine room (if any) ...	<i>48</i>	-
Number of water ballast tanks, and their capacity in tons ... <i>Eight 1005 tons total</i>			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck } *6760* tons.
at side amidships to bottom of keel ... }
Ditto per inch immersion at same } *33.16* tons.
depth ...

PARTICULARS OF ENGINES (if any).

No. of Engines.	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
<i>Three</i>	<i>Triple Expansion Direct Acting three crank engines</i>	<i>British</i>	<i>Engines. 1902</i>	<i>Dunsmuir & Jackson Ltd. Govan</i>	<i>Three 24" 40" 65"</i>	<i>45"</i>	<i>321 1800 10 knots.</i>
	<i>Boilers. Two Iron or Steel Pressure when loaded 180 lbs</i>						

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	<i>2985.90</i>	On account of space required for propelling power	<i>1023.04</i>
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	<i>113.48</i>
Space or spaces between Decks ...		These spaces are the following, viz.:—	
Poop ...	<i>48.91</i>	<i>Forecastle Side & Round Houses</i>	
Forecastle ...	<i>17.21</i>	Deductions under Section 79 of the Merchant Shipping Act, 1894, as follows:—	
Round House ...	<i>82.09</i>	Cubic Metres	
Other closed-in spaces, if any, as follows:—	<i>24.16</i>	<i>Master 6.05</i>	
<i>Side House</i>		<i>Chart House 4.47</i>	<i>32.54</i>
<i>Excess of Hatchway</i>	<i>38.72</i>	<i>Boon's Store 13.64</i>	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894, if required.		<i>" " 8.38</i>	
Gross Tonnage ...	<i>3196.99</i>	Total Deductions ...	<i>1169.06</i>
Deductions, as per Contra ...	<i>1169.06</i>		
Registered Tonnage ...	<i>2027.93</i>		

Name of Master

Certificate of { Service No. Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

*British & Foreign Steamship Co. Ltd. of 67 South John Street, Liverpool } 64 shares.
Thos. F. Harrison of above address Manager.*

Dated *19 October 1902*



© 2020

Lloyd's Register Foundation

W681-0097