

Lloyd's Register of Shipping.



Port

DAIREN

No. 4378

February 1st, 1934.

This is to Certify that

John 5:19

the undersigned Surveyor to this Society did at the request of

The measurements were taken at the S.M.R.Co.'s storage tank No.1 and measured before loading 5.172 metres eqs 942.674 cub metres F.W. with oil temp 8.3°C and density .9284 i.e.  $942.674 \times .9284$  eqs 875.178 cub metres oil in tank. Remaining in tank 3.377 metres equals 615.153 metres F.W. with oil temp 9.6°C and density .9279 i.e.  $615.153 \times .9279$  eqs 570.800 cub metres oil in tank. Therefore 875.178 minus 570.800 eqs 304.378 cub metres from tank.

Measurements taken at the S.M.R.Co.'s storage tank No.1 and measured before loading 1.216 metres cgs 219.921 cub metres F.W. with oil temp 7.4°C and density .929 i.e. 219.921 x .929 equals 204.306 cub metres oil in tank. Remaining in tank after loading .722 metres cgs 130.747 cub metres F.W. with oil temp 5.7°C and density .9302 i.e. 130.747 x .9302 equals 121.620 cub metres oil. Therefore 204.306 minus 121.620 cgs 82.686 cub metres plus 304.378 from 1st lot equals 387.064 divided by 1.016 equals 380.968 tons oil from tank less .368 for flexible hose making total in ship's tank 380.4 long tons (Three hundred and eighty decimal four long tons) shipped.

Wllage measurements taken 19 hours after loading had been completed with Draft Fore 9'-7" Draft aft 18'-5" list  $1^{\circ}$  to Port Mean temp  $6.6^{\circ}\text{C}$  and density .9296 Sea temp  $+1.1^{\circ}\text{C}$  Air temp  $+1.1^{\circ}\text{C}$

17 1/2" 17"

Sufficient allowance has been made for expansion during present voyage to Europe.

1614

1640

I hereby certify that all the above measurements together with temp and density were taken by the undersigned and show the amount of Bean Oil loaded into the Starboard After Deep Tank of the S/S "KAMO MARU" of Tokio, on January 30th, 1954.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :—

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Committee or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

(Rpt. 10.) 10m, 7, 33.

Survey Fee \$60.00  
Expenses \$5.00