

S.S. "OLDERKERK" ex "SESOSTRIS".

This vessel was built in 1916 by Messrs. Flensburg Schiffsbau, Ges., and classed with the Germanischer Lloyd, and is now at Rotterdam undergoing survey with a view to classification with this Society.

The plan of the shafting was approved in the Secretary's letter E of 25th instant.

A plan of the boilers has now been forwarded which meets the requirements of the Rules in force, when the boilers were constructed, for the original working pressure of 13 kg. per sq. cm., with the exception of the furnaces the scantlings of which, on account of the low minimum tensile strength of the material, are slightly below what would be required.

It is submitted that provided the boilers be examined throughout and be found in good and safe working conditions and in accordance with the requirements of the Rules, the scantlings be in accordance with the plan, and the furnaces be found to shew no sign of strain, these boilers might be accepted and a working pressure of 13 kg. per sq. cm. (185 lbs. per sq. in.) assigned.

Return 1 plan.

Retain 1 plan for reference.


L.Y.

[Signature]

Dr. 29th

J.M.

L.Y.
27. 8. 21.



© 2020

Lloyd's Register
Foundation

W69-0050