

COPY.

3rd.March, 1904.

Dear Sirs,

With reference to the Rules of this Society for Electric Light, and to paragraphs 10 and 11 thereof, requiring in vessels fitted with Electric Light the wires in cargo spaces, coal bunkers, or spaces which may at any time be used for carrying cargo, stores or baggage, or which are not at all times accessible, to be strongly protected against damage preferable by iron casings, I beg to state for your information that it is considered by the Committee that so-called armouring by small wires is not sufficient protection to allow of casing &c to be dispensed with. If, however, the armouring is substantial, of wires not less in size than No.14 L.S.G., and if the armoured cables are properly secured in places such as under decks where their position is some protection, then such armouring will be considered to be sufficient protection to admit of casing being dispensed with.


Yours faithfully,

(Sgd). Thos Warren

For the Surveyors.

Messrs J.L.Thompson & Sons Ltd.,

North Sands.



© 2020

Lloyd's Register  
Foundation

W695-0244

*Spliced, soldered and insulated with approved m*