

Do. of Bridge House
Do. of Forecastle
Do. of Houses on Dk.
Do. of Houses of Hatchways

Transverse Number 88.0
Length on deck from fore part of stem to after part of stern post 442.0

When built 1905
By whom built 4.

29. 8. 19

TWIN SCREW STEAMER "PRINCESS".

EQUIPMENT.

In response to a cable sent to the Calcutta Surveyors on the 14th July requesting them to forward the Owners' proposals regarding the deficiency in the equipment of the vessel, a cable was received on the 24th July stating that the Admiralty were the Owners.

Mr. R.R.G. Chisholm, of the Ministry of Shipping, was consulted and it was pointed out to him that the equipment of the vessel was not in accordance with the requirements of the Rules, and in order that the vessel might obtain the full class of 100A1, it will be necessary to have the equipment on the vessel altered to comply with the rule requirements.

Mr. Chisholm stated that they desired that the vessel should have the full class of 100A1 and that the necessary modifications would be made to the equipment on the vessel. He requested that he should be supplied with the particulars of the equipment at present on the vessel and also the full Rule Equipment.

A comparison of the Rule Equipment and that on the ship is as follows:-

On Ship.

Rule.

	cwts.	qrs.	lbs.			cwts.	qrs.	lbs.	
Bower	60	0	2	Stockless.	1 Bower	77	0	0	stockless
"	60	0	2	"	1 "	77	0	0	"
"	60	0	0	"	1 "	65	2	0	"
Stream	22	0	0	Ex stock	1 Stream	22	0	0	ex stock
Kedge	10	0	0	"	1 Kedge	10	0	0	"
5 fms. 2 5/16 (mean) stud link cable.					300 fms. 2 7/16 stud link cable.				
" 15.7 hemp rope					120 " 15/16" stream chain				
at 4 1/2" steel wire					for 5" steel wire				
at 3 1/2" " "					130 " towline (15" hemp or				
at 3 1/2" " "					5 3/4" steel wire				
at 2 1/2" " "					2 at 100 fms. of 8" Hawser				
at 10" Ropes					2 at 100 " of 8" Warps				
2 at 9 3/4" " "									
2 at 8 " " "									
1 at 9 1/2" " "									

Lloyd's Register
Foundation 002

Angles on upper edge
Spacing
BEAMS, Forecastle Deck, Angle Bulk Head
Tie Plates
Deck, Material and thickness

