

Hamburg Report Nr. 1566A

of Hamburg

22nd of September, 1923.

----- C. P r i e s s, -----

the owners representative survey afloat at Hamburg the
vessel "Sokoto" 3698/2811 Tons of London

Damage alleged sustained through a mahogany log to the
mast whilst loading at Hamburg 30th of August, 1923.-

For full particulars having reference to this casualty
entries in vessels Log-Book,---

On the 30th of August and subsequent Dates surveyed
vessel on the yard of Blehm and Voss and found on examina-
the Main-mast broken in way of deck and on top, two derricks
Rails and stanchions in way of No3 hatchway damaged, the No3
coaming bent fore and aft, the trust shaft recess damaged
two awning and one hold stanchion bent.-----

It was recommended, that the main-mast be removed and
replaced by new plates in way of deck and a new topmast and re-
d, rigging repaired and replaced, -that the two derricks be
d and repaired, that the damaged rail be repaired, that the
ings of No3 hatchway be faired and repaired, that the thrust-
recess be repaired by fairing of two plates and one angle
two tunnel stiffeners be riveted, that the three bent pil-
be faired, that the after end of wood-deck be repaired and
laked and that all minor repairs in connection to the above
rs being carried out and repaired parts tested and recoated.

The vessel being now restored to the same sound and effie-
tion as before the casualty occurred.---

£ 2- 10 - 0 (Two Pound ten)