

COPY

LLOYD'S REGISTER OF SHIPPING.

PORT.

SYDNEY. N.S.W.

24th January 1927.

THIS IS TO CERTIFY that

E. L. CARTWRIGHT,

the undersigned Surveyor to this Society did at the request of

The Owners,

survey the Steel Screw Steamer "E A L A V A" of Sydney N.S.W. 413 Gross Registered Tons, for the purpose of ascertaining the nature and extent of the Damage stated to have been sustained to the vessel while manoeuvring in Woolloomooloo Bay, Sydney N.S.W. on the 29th October 1926 by colliding with the T.S.S. "Otranto".

For further particulars see Log Books.

Upon examination, vessel afloat in Sydney Harbour on the 30th December 1926 and subsequent dates, the undersigned

FOUND.

RECOMMENDED.

Stem bar at forecastle deck bent aft.

To be faired in place.

Upper forecastle side shell plate and edge plate (combined) No.1 from stem, port and starboard sides deeply indented.

To be cut and renewed above waterway bar, and lower portion of plates be faired in place.

No.1 forecastle deck beam from stem slightly bent.

To be faired in place.

No.1 side frame from stem with beam bracket, Port Side, buckled.

To be renewed.

Locker in Port Side forecastle sprung and damaged.

To be repaired.

Stanchions and rails on forecastle head bent and broken

To be faired and renewed as found necessary.



© 2020

Lloyd's Register Foundation

W703 - 01662

COPY

2.

S. S. "GALAVA" (Continued)

FOUND.

ring check bed plate and bearers
stem buckled.

castle deck plate and waterway
in way of stem on port side
dled.

wood rubber and face bar on
board quarter split and buckled.

ark plating and rail on star-
board quarter slightly indented.

mooring check, starboard side,
broken with bed and bearers.

topmast stay broken.

ing screw on foremast broken.

RECOMMENDED.

To be faired or renewed as
found necessary.

To be renewed.

To be cut out and renewed.

To be faired in place.

To be renewed.

To be renewed.

To be renewed.

Recommendations are necessary in order to place the vessel in
same condition as she was in, previous to sustaining the before
Damage, and have now been seen satisfactorily completed.

(SGD) E. L. CARTWRIGHT,

SURVEYOR TO LLOYD'S REGISTER.



© 2020

Lloyd's Register

W703 - 0166 2