

S.S. "MONTE GRAPPA", MESSRS. STABILIMENTO TECNICO TRIESTINO'S  
NO. 565.

A letter has been received from the Trieste  
Surveyors stating that on verification of the anchors placed  
on board the above vessel, it was found that the weight of  
stream anchor is less than required by the Rules.

It is noted that the equipment numeral is 41596.

On board S.S. "MONTE GRAPPA".                      As per Rules.

1st bower anchor stockless	73. 0. 1	72. 2. 0.
2nd " " "	71. 1. 25	72. 2. 0.
3rd " " "	71. 0. 17	62. 0. 0.
Stream anchor (Anchor 19.3. 4.)		(Anchor 20.2. 0)
(Stock 6.2.26.)	26. 2. 2.	(Stock 5.0.14) 25. 2.14.
Kedge Anchor (Anchor 9.1. 7.)		(Anchor 9.0. 0)
(Stock 2.2. 2.)	11. 3. 9.	(Stock 2.1. 0) 11. 1. 0.
	253. 3. 26.	243. 3.14.

It will be observed that while the weight, ex stock, of  
the stream anchor supplied, is less than required by the Rules,  
the total weight of that anchor is greater than that required  
by the Rules. Also the collective weight of the anchors supplied  
is much in excess of the Rules requirements.

Submitted that in the circumstances the stream  
anchor as supplied may be approved.

TUE. OCT. 12 1920

*Approved. [Signature]*

*R.M.M.*

8.10.20.

*[Signature]*

30.9.20  
13/10/20



© 2020

Lloyd's Register  
Foundation