

250,1,10.

F.E.

Received by Chief Ship Surveyor 18/2/10

Received from Chief Ship Surveyor

VESSEL'S NAME *Stl. Y. S. S. "Kangatira"*Rpt. *Bel. & Gls* No. *6723*
28568

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Transverse No. *94.83.*Depth "d" *18.84*Framing: Table No. *3, page 15.*Description *Channel frame with reverse frame as approved*Longitudinal No. *45233, page 2*
*Table 18*Proportions Length = *9.4*
Depth =Bridge Deck Sheerstrake *as per Rule.*

The flat plate keel is 1" less in width and .08 less in thickness than required by the Rules but compensated for by fitting an outside rubbing bar, in other respects

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed **†100A1 ("Steel") "Shelter Deck** with freeboard," as recommended. The Summer freeboard of *5'-11"* from centre of disc to top of statutory deck line at *upper* deck, now marked on the vessel's sides, to be inserted in the classification certificate, and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying verification form to be inserted in the certificate of classification.

†100A1 ("Steel") "Shelter Deck with freeboard"
2 Dks (stl.) & Shelter Deck (stl. w.s.)

WB - all DB a 11' 6" E & B 77' f 221' = 1490t
FK & BK 1 3/4", 8 BHD. Cem. Lloyd's A & C.P. B 180' F 50'

The Surveyor should be informed that this vessel should have been reported on form 18

PILLARS, in 'tween Deck, size and spacing

" Hold

" Quarter 'tween Dks., "

" in Hold

" spaced 20 to 26 ft as per plan "

Angle on ditto

© 2020

Register
Foundation

W720-0042