

MEMORANDUM.

The Screw Wood Steamer "WAR MARVEL" No. 2 in the
Element of the Register Book.

Dimensions:- 300' B.P. x 48' Moulded x 28.5' Moulded.

This vessel was built by Messrs. The National
building Co. at Orange, Texas, for Messrs. The
ard S.S. Co. and is classed * 10 A.1. She was completed
1918.

The vessel has two laid decks, a long poop and
castle. The machinery is fitted aft, bulkheads are fitted
the fore and after ends of the machinery and a collision
head^{is} also fitted. Two bulkheads are fitted about midway
ween the Collision and Machinery Bulkheads, these two
kheads extend only to the 2nd Deck and were originally
ended to form a deep tank for the carrying of water
last.

The stem and stern post are of oak, the remainder of the/
the structure being of long leaf Yellow Pine. timber

The centre keelson is of steel plates and angles.
keel, floors & beams are of the usual type used in wood
sels. The outside planking is reinforced by 2^{diagonal} thicknesses of/
nking, each 1 1/4" thick and fitted^{next the timbers} at right angles to one
ther. The ceiling is edge bolted from lower turn of
ge to upper deck, the wales being also edge bolted.

The rudder is of single plate type with cast
el frame. The gudgeons for receiving the pintles are
cast steel and are connected to the wood stern post with
e through bolts 1 1/4" diameter clenched at each end.



© 2020

Lloyd's Register
Foundation

W721-0161

Buel
ed Voy
ars of C
cise as
CHARACTER,
Special Surve
Last Survey an
Medical Survey
AI-8
AI-
eeboard (n
Ship an
rvice fo
y whom
tueli
on d
d-d
ca
er Items
Cop
Boa
Mas
Con
(
Sail
Equ
Anc
Cab
Hav
Sta
essel i
o rema
at
9
za