

S. S. "War Monarch" No 39 in Supplement.

Capt. L. Ward representing the Owners. The Commanding Officer has called at this Office with a view to increasing the area of the rudder of this vessel.

The particulars of the rudder as ascertained from San Francisco Surveyors are as follows:- Area 100 sq. ft., distance of the centre of gravity abaft centre line of pinches 3.98 feet, giving an "A x D" of 398.

The speed of the vessel as given on the First Entry is 10 1/2 knots, and the rudder head is 10 1/2" diameter, as required by the Rules for the "A x D" and the speed of Vessel as given above.

The grade A x D is above 505 and not exceeding 5% of Table 22 of the Rules it is not seen how the area of the rudder could be appreciably increased without requiring an increase in the diameter of the rudder head.

It is submitted Capt. L. Ward by informed accordingly.

C. F.  
P. 10. 17.

B. O. P.

Owners: 8/10/17.  
pc S. to  
from S. to 7/10/17.  
C. F. nod. 8. 10. 17.  
pc nylk.



© 2021

Lloyd's Register  
Foundation