

## REPORT of SURVEY for REPAIRS, &amp;c.

Date of writing Report 28-7-1917 When handed in at Local Office 28-7-1917 Port of SUNDERLAND  
 No. in Survey held at SUNDERLAND Date, First Survey 14-7-17 Last Survey 27-7-1917  
 Reg. Book. on the Wood, Iron or Steel S.S. THAMES Master J. C. CARLING  
 (No. of Visits SIX)

484 TONNAGE:- Built at GOOLE By whom GOOLE S.B. & REPC CO. LD. When 1910 MONTH. T  
 GROSS 403 Owners DALE COASTERS LTD. Port belonging to HULL  
 UNDER DECK 271 Owners' Address (LYTHGOE AMUNDSEN & CO. MGRS.)  
 NET 174 (if not already recorded in Appendix to Register Book.)

Surveyed Afloat or in Dry Dock? YES Name of Dock COMB N°1 Destined Voyage COASTING

W.B. = Cell D B o D B a feet: u E & B feet: f feet: }  
 total capacity tons. FPT tons; APT tons; MT feet tons. }

N.B.—All alterations in the existing records should be underlined.

If the Vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner bottom plating, especially in the boiler space.

Last Report, No. 26796 Port Sld

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

CHARACTER. * for Special Survey. Date of last Survey and of Periodical Survey.	Years Assigned expired.	Machinery and Boiler Survey (including date of N.B. if any).
100 A. 1. 9-16. S.S. DUB N° 1-14.		LMC. 6-16 T.S. 6-16

(Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported, the particulars should be clearly stated in the space provided on the back of this form. State also the dates and initials of any letters respecting this case.

Society's Freeboard (if assigned) as painted on Ship and now verified 4 ft 5 ins.

In damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and to whom and why they were declined? YES TO SUPERVISOR, NOT REQUIRED Was a damage report made by anyone else? If so, by whom? MR METCALF FOR UNDERWRITERS

REPAIRS, OR EXAMINATION AS PER RULE, FOR DAMAGE stated to have been caused by grounding at Cannes 9.3.17.

Vessel placed in dry dock, bottom and rudder cleaned examined and coated.  
 Rudder lifted bottom pintle renewed, remainder polished and rudder reshipped.  
 Part ceiling on tank top lifted N° 1 & 2 tanks tested, riveting and caulking made good as found necessary and ceiling relaid. Forepeak tank tested on completion of repairs.  
 Four shell plates removed, faired and refitted A.P. B. 15. C.P. C. 25.  
 One shell plate faired in place B. 25.  
 Three frames removed faired and refitted, three faired in place starboard side and four faired in place on port side. Forward length of bilge keel bulb starboard side removed, faired and refitted.  
 Riveting & caulking of bottom overhauled and made good as found necessary.

SUMMARY OF DAMAGE REPAIRS :—		Plates.	Frames.	R. Frames.	Floors.	Beams.	Str. Plates.	Dk. Plates.	Other Items :—
Renewed	...	1				2 knees	1		
Removed and Faired or Repaired	...	4	3	✓	✓		✓	✓	
Faired or Repaired in place	...	6	10			1 knee	1		minor repairs to bulwarks

PRESENT CONDITION OF THE		Stringers	Inner Bottom Plating	State if Tanks have been examined inside	State if Tanks now tested	Bulkheads	Ceiling	Cement on deck (State which.)	Rudder	Steering gear and its connections	Windlass	Have Pumps now been examined and found efficient?	Have Sluice Valves now been examined and found efficient?	Have Watertight Doors now been examined and found efficient?
Decks	GOOD		PART SEEN	N.O.	YES	GOOD		✓	GOOD			✓	✓	✓
Caulking of Decks	✓													
Waterways	✓													
Coamings	✓													
Beams & Fastenings	PART SEEN													
Outside Plating	✓													
Caulking of ditto.	✓													
Rivets	✓													
Breasthooks & Crutches	✓													
Transoms	✓													
Frames	✓													
Reverse Frames	✓													
Floors	✓													
Keelsons	✓													

Dbng. Plates under Sounding Pipes	✓	Copper, or Y.M. of Wood Vessels (State if on Felt.)	
Engine Room Skylight	GOOD	When put on, Month	Year
Coal Bunkers, Open'gs, Lids, &c.	✓	Boats	GOOD
Scuppers	✓	Masts, &c.	✓
Cargo Hatchways	✓	Condition, how ascertained	FROM D.K.
Hatches	✓	(State if wedges removed)	✓
Planking of Wood Vessels	✓	Sails	✓
Caulking ditto	✓	Equipment letter	F
Treenails	✓	Anchors, No. of	28. 15. 1K
Breasthooks & Stemson ditto	✓	Cables (State if now ranged)	✓
Transoms, Pointers, & Crutches ditto	✓	„ length „ size „ (on board)	✓
Timbers of Frame at openings ditto	✓	„ Rule length „ size „	✓
Ditto ditto at other places ditto	✓	Hawser & Warps	STATED
Stringers, Clamps & Shells ditto	✓	Standing & Running Rigging	GOOD
Salting ditto	(State if examined.)		

## General Observations, Opinion as to Class, Recommendation, &amp;c.:—

State clearly whether any, and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—“to remain as now classed in the Register Book without fresh record of Survey,” “to remain as classed and to have record of survey, 1, 15,” or “to remain as classed and to have record of survey, 1, 15, and the notations of ss No. 1-15 and ptND15, &c.”

This vessel is now in good and efficient condition and eligible, in my opinion, to remain as classed with fresh record of survey 7-17.

Survey Fee (per Section 28) £ : : Fees applied for, 8 AUG 1917

Special Damage or Repair Fee (if any) (per Sec. 28) £ 3 : 3 : 0 Received by me, 29.5.18

Travelling Expenses (if chargeable) £ : : 30-5-18

Second Surveyor's Fee (if any) £ : : Surveyor to Lloyd's Register of Shipping.

Committee's Minute TUE. 14 AUG. 1917

Character Assigned 10001

Surveyor to Lloyd's Register of Shipping.



Lloyd's Register Foundation

W727-0095



