

COPY

OF VANCOUVER, B. C.

JULY 19th. 1921.

THIS IS TO CERTIFY,

Evan Edwards,

the undersigned Surveyor to this Society did at the request of the Owner's Representative survey the STEEL SCREW STEAMER "CANADIAN EXPORTER", of Montreal, for the purpose of ascertaining the nature and extent of damage stated to have been sustained through the vessel striking the Dominion Government Wharf, in the Harbour of Vancouver, B. C., on July 30th. 1920.

FOR FURTHER PARTICULARS SEE LOG BOOK.

On the 13th. July, the vessel lying in dry dock at Victoria, B. C., and subsequently afloat at the wharf of Messrs. Yarrows Ltd., Victoria, B. C., made examination, found and recommended as follows:-

FOUND

Shell Plate G.No.4 Port Side buckled.

Bulkhead at after end of No. 1 Hold, a number of rivets and some caulking started in way of shell plate G. No. 4 Port Side.

Two Frames (one on either side of bulkhead) in way of shell plate G. No.4 port side slightly set in.

RECOMMENDED

To be faired in place, and the riveting and caulking tested.

Riveting and caulking to be tested, started rivets to be cut out and renewed, started caulking to be re-caulked.

To be faired in place.

On completion of repairs all new & disturbed material to be re-coated.

SURVEYOR TO LLOYD'S REGISTER.

Lloyd's Register
Foundation

W734 - 0070