

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) T.W.B.K.

Official Number.	Name of Ship.	No., Date, and Port of Registry.					
115645	"Trewyn"	² 1903	St. Ives.				
No., Date, and Port of Previous Registry (if any). <u>First Registry</u>							
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.			
British	Steam Screw.	South Shields	1903	John Readhead & Sons South Shields.			
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	323	Feet.	Tenths.		
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	322	9	0		
Rigged ...	Schooner	Main breadth to outside of plank ...	47	1			
Stern ...	Elliptic	Depth in hold from tonnage deck to ceiling at midships ...	23	75			
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	—	—	—		
Galleries ...	None	Depth from top of beam amidships to top of keel ...	25	9			
Head ...	None	Depth from top of deck at side amidships to bottom of keel	25	2			
Framework and description of vessel ...	Steel	Round of beam ...	—	9			
Number of Bulkheads ...	Five	Length of engine room (if any) ...	44	1			
Number of water ballast tanks, and their capacity in tons ...	Six 763 tons						
PARTICULARS OF DISPLACEMENT.							
Total to quarter the depth from weather deck at side amidships to bottom of keel ...			6530 tons.	Ditto per inch immersion at same depth ... } 319 tons.			
PARTICULARS OF ENGINES (if any).							
No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
Three	Engines. Triple expansion, Direct acting. Inverted Boilers. Number.....Two Iron or Steel.....Steel Pressure when loaded 160 lbs	British	Engines. 1903 Boilers. 1903	Engines. John Readhead & Sons Boilers. South Shields.	Three 24" 40" 64"	42"	300 1200 10 knots.
PARTICULARS OF TONNAGE.							
GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.		
Under Tonnage Deck ...		2915.93	On account of space required for propelling power		986.82		
Closed-in spaces above the Tonnage Deck, if any			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		48.88		
Space or spaces between Decks ...			These spaces are the following, viz.:—				
Poop ...			Deductions under Section 79 of the Merchant Shipping Act, 1894, as follows:—				
Forecastle ...		46.52	Cubic Metres. <u>Boon's Store</u> 16.20		28.63		
Deck Houses ...		82.68	<u>Master's Berth</u> 7.72				
Other closed-in spaces, if any, as follows:—		38.69	<u>Chart Room</u> 4.71				
Excess Hatchways			Total Deductions ...		1094.33		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894, if required.							
Gross Tonnage ...		3083.82					
Deductions, as per Contra ...		1094.33					
Registered Tonnage ...		1989.49					
Name of Master	Samuel Gorley	Certificate of	Service No. —	Competency No. —			
No. of Owners							
Name, Residence, and Description of Managing Owner if there are more owners than one.	The Hain Steamship Co. Ltd of St. Ives, Cornwall. — 64 Shares						
	Edward Hain, M.P. of St. Ives, Cornwall.						
	Manager.						
Dated	9 th March 1903						