

25<sup>th</sup> February 15

Charles R. Hughes

Captain Seagrave Representing W. A. India  
Office Survey the steel screw steamed  
Treatberg of Bremen, 1892 Tons.  
Gross Register, while lying afloat in the Survey  
Commercial Docks, London, in order to ascertain  
the nature and extent of damage sustained to  
the hull of the vessel at some unknown date,  
particulars of which could not be obtained.

The vessel was examined afloat on the 21<sup>st</sup>  
January 1915 and subsequent dates when the  
following damage was found to have been  
sustained on the Starboard side in way of  
After Hold.

Found

Two shell plates in 2<sup>nd</sup>  
strake below sheer, indented.  
Three frames set in

Recommended

To be removed, faired and  
replaced.  
To be faired in place.

P.T.O.



© 2020

Lloyd's Register  
Foundation

W439-0133 (1/2)



Inspection

(2)

Inspected

Recommended.

board side left  
frame fractured.

To be released, fairied and  
efficiently strapped.

shell lugs and  
ingen bar; cut on

To be released, fairied and  
refilled.

anges plate to be  
removed

Deal with as found neces-  
sary.

shell plates found  
cracked in N° 34 & 35

Then two shell plates to be  
removed, fairied and replaced.

Temporary repairs have now been carried out, by  
efficiently strapping fractured frame and hardening  
it started rivets and caulking landing edges of  
all plates in way of damage.

For L. S. S. C.

C. N. Hughes  
Surveyor to Lloyd's Register.



© 2020

Lloyd's Register  
Foundation

W739-0133(2/2)