

Vessel built at Vancouver B.C. By whom Western Canada Shipbuilding Co. Ltd.  
1425  
322  
Engines made at Toronto  
Boilers, where made  
Boilers ✓  
Owners  
185

Port  
Examination and Repairs (if any)

Port. GIBRALTAR.

11th, February, 1920.

THIS IS TO CERTIFY that

Engineer Captain L.J. Stephens, C.E.B., R.N.

undersigned Surveyor to this Society did at the request of  
Agents, Messrs Smith Inossi & Co., and with the consent of the  
Master, survey the Machinery of the S.S. "WAR CASCO".

following defects have been surveyed and are being made good:-

- Coupling of main shafting broken and tested for alignment.
- All coupling bolts dressed up and renewed 1 No.
- Main circulator seating refitted and new spindle made.
- Auxiliary Condenser: new cast iron discharge pipe made.
- Winches. New spindle brackets and spindles 2 No. made.
- New valve lever brackets 4 No. made
- Tie rods straightened and repaired 4 No.
- New reversing brackets 4 No. made.
- New flange fitted to steam valve 1 No.
- Steel studs for main steam pipes 6 No.
- New clutch arms for winches 2 No.
- New metal gauge adaptors 2 No. for Boilers.
- Ballast pump plungers re-grooved 2 No.
- Screen bulkhead refastened.
- Engine Room gratings re-set.
- Boiler Room gratings re-set.
- Several indicator pipes rebrazed, replaced, and relagged.
- About 8 No. steam and water pipes removed and re-set for  
Constructive Department owing to stanchions being fitted.
- Main steam pipes re-jointed 2 No.

*Richard V. Stephens*

Engineer Surveyor to Lloyds Register.

© 2019 Lloyd's Register Foundation

Repair Fee (if any)  
Received by me