

PRINCIPAL DIMENSIONS

LENGTH B.P. 300' 0"
BREADTH EXTREME 51' 9"
DEPTH IN HOLD TO TANK TOP 22' 3 1/2"
DEPTH MOULDED 24' 10"

SCALE 1/2" = 1 FOOT

"Snowdonian"

13 CAMBER.

22.3.07

28 CLASS 100 A1 LLOYDS.

9.4.07 THREE DECK RULE

NORMAL FREEBOARD

SCANTLING NUMBERS

HALF BREADTH 25.77
DEPTH 25.90
HALF GIRTH 48.28
99.95
7.00
92.95

RULE LENGTH 357.7

2 DECK NUMERAL 357.52

3 DECK NUMERAL 332.48

BREADTHS IN LENGTH 6.94

DEPTHS IN LENGTH 13.81

EQUIPMENT NUMBER 39137

	FULL BEAMS	BULB ANGLE	9 x 3 1/2 x 1/2
(IN BRIDGE)	DO	DO	9 1/2 x 3 1/2 x 1/2
	HALF BEAMS	DO	7 1/2 x 3 1/2 x 1/2
(IN BRIDGE)	DO	DO	8 x 3 1/2 x 1/2
	HATCH BEAMS	DO	9 x 3 1/2 x 1/2
(IN BRIDGE)	DO	DO	9 1/2 x 3 1/2 x 1/2

STEEL CENTRE DIVISION 20" CLEAR OF HATCHES
PLATES FLANGED
FLANGES 10 x 3 1/2 50 APART.

HORIZONTAL STIFFENER
IN FORWARD HOLDS ONLY

EQUIPMENT = W

- 2 BOWERS 52 1/2 OUT STOCKLESS
- 1 DO 44 1/2
- 1 STREAM 14 EX STOCK
- 1 KEDGE 6
- 270 FATHOMS 2 1/2 STUD CHAIN CABLE
- 90 DO 4 1/2 MOORING WIRE
- 120 DO 4 1/2 STEEL TONLINE
- 2-90 DO 2 1/2 DO HAUSERS
- 2-90 DO 7 MANILLA WARPS

FRAMES (BETWEEN PEAK BHDS) B.A. 10 x 3 1/2 x 20-25 APART, ALTERNATE BULB ANGLE FRAMES.

EXTENDED TO BRIDGE DECK AND AN ANGLE 4 x 3 1/2 x 20 FITTED BETWEEN EACH BULB ANGLE FRAME
ALTERNATE REVERSE FRAMES CARRIED TO FORECASTLE DECK.

FRAMES AT ENDS. IN PEAKS 8 1/2 x 3 1/2 x 20

REV FRAMES DO DO 4 x 3 1/2 x 20

TANK REVERSE FRAMES DOUBLE UNDER ENGINES AND ON BOILER BEARERS

BULKHEADS 10 x 20 (FLOORS BY RULE 28 x 20)

STEM 11 x 2 1/2 STERN FRAME 11 x 6 1/4 RUDDER 9 1/2 x 4 1/2

THREE ROWS OF RIVETS BELOW BOSS

38 1/2 - Rule 3 1/2
TANK MARGIN PLATE 10 (10 BOILER SPACE) BUTTS DOUBLE RIV LAPS.

(4) MIDDLE LINE STRAKE 10 FOR 1/2 L TO 20 (10 BOILER SPACE) BUTTS DOUBLE RIV LAPS
TANK TOP IN HOLDS 20 FOR 1/2 L TO 20; IN ENGINE SPACE 20; IN BOILER SPACE 20 IRON
TANK TOP BUTTS DOUBLE RIV LAPS

DOUBLE 22" CEILING

3 1/2 x 3 1/2 x 20

42 x 15

42 x 15

42 x 15

FLOORS 20 (10 BOILER SPACE IRON)

3 1/2 x 3 1/2 x 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

13 FOR 1/2 L TO 20

RICHARDSON DUEK & CO
SHIPBUILDERS
STOCKTON-ON-TEES

BOSS PLATE AND PLATE ABOVE & BELOW 20 THICKER THAN PLATES AMIDSHIPS. BUTTS LAPPED AND TREBLERIV
SHELL (EX PLATE KEEL & GARB) B, C, D, TO BE REDUCED 20 IN WAY OF DOUBLE BOTTOM WHERE 20 OR ABOVE.
ALL SHELL BUTTS LAPPED AND TREBLERIVETTED, QUADRUPEL WHERE OVER RULE WIDTH FOR 1/2 L.
INCREASES IN TANK UNDER BOILERS (WHERE NOT SHOWN) AS PER RULES.



15-3-07 N°588

Richardson Dock

No 588

Midship Section

"Snowdonian"

Mod. Rpt. No. 5257

RECEIVED
MAY 18 1880
LLOYD'S REGISTER OF SHIPING

RECEIVED
MAY 18 1880
LLOYD'S REGISTER OF SHIPING



W755-0215



© 2020

Lloyd's Register
Foundation