

Correspondence.—State dates and initials of letters respecting this case (Reference should be made to any correspondence connected with this case)

M. 10.11.05. 20.11.05. 1.12.05. 23.2.05

Workmanship. Are the butts of plating planed or otherwise fitted? *Lapped & planed.*

Is the riveted work properly closed? *Yes*

Are the liners between the frames and plates solid single pieces? *Yes*

to plate, &c., conform well to each other? *Yes*

Do the holes for riveting plate to frames, butt straps, or plate

from the faying surfaces? *Yes*

Are the rivet holes well and sufficiently countersunk in the plate and punched

Are the butts of Plating, Stringers, &c., properly shifted and strapped? *Yes*

Do any rivets break into or through the seams or butts of plating? *a few*

Have all the upper and weather decks been tested as required by the Rules (Sec. 23, par. 24)? *Yes*

State results of tests

Have all the gutterways been tested as required by the Rules (Sec. 23, par. 25)? *Yes*

State results of tests

General Remarks (State quality of workmanship, &c.)

This vessel has been built in accordance with the Rules, the approved plans and the Secretary's letters quoted above.

The workmanship and materials are good throughout.

No. 1, 2 & 4 holds are insulated for the carriage of frozen meat cargoes.

(S/S. Star of Scotland)

Belfast Report 5807.

This vessel was built from the same series as above, but the scantlings are altered slightly.

The Surveyor should state the Number of Report and Name of any Sister Vessel.

PARTICULARS FOR RECORD in the REGISTER BOOK.—Length of Poop _____ ft., R.Q.D. or Break _____ ft., Bridge Dk. _____ ft., F'castle _____ ft. (in feet and tenths). When the Poop is joined to the B.D., this should be distinctly stated *Complete Shelter Deck.*

No. and Material of Decks (if Iron or Steel) and whether wholly or partially covered with wood, and No. of tiers of Beams (this information is to be given as it should appear in the Register Book) *2 Dks (Stc) and Shelter Dk (Steel - w.s) and deep framing*

Official No. _____; Signal Letters _____

How are the surfaces preserved from oxidation? Inside *Portland Cement & Paint* Outside *Paint*

PARTICULARS OF WATER BALLAST.—State whether the Double bottom is constructed on the cellular system or with g'rders on floors *Cell. Stb.*

Where fitted.	*Length. Feet.	Water Capacity. Tons.	Where fitted.	*Length. Feet.	Water Capacity. Tons.
Double bottom, aft,	<i>110.6</i>	<i>335</i>	Fore peak tank,		
Double bottom, under Engines and Boilers,	<i>69.4</i>	<i>233</i>	After peak tank,	<i>16</i>	<i>60</i>
Double bottom, if under Engines only,			Midship deep tank,		
Double bottom, if under Boilers only,			Other tanks, if fitted,		
Double bottom, forward,	<i>199.4</i>	<i>695</i>	(If necessary, furnish further information by sketch.)		

* The wells are not to be included in the lengths of the tanks.

State whether the above have been tested as required by the Rules

Yes

Order for Special Survey No. *511*

Date *9 June 1906*

No. *235* in builder's yard.

DATES of Surveys held while building

1905 Nov 10, Dec 7, 12, 15, 21, 22. 1906 Jan 2, 4, 9, 17, 26, 30. Feb 9, 15, 9, 15. 16, 27, 28. Mar. 2, 6, 8, 13, 19, 26, 27, 29. Apr. 4, 9, 13, 30. May 1, 10, 14, 16, 18, 22, 25, 30. June 5, 8, 11, 13, 18, 29, 22, 26. July 2, 11, 24, 26, 30. Aug 1, 3, 7, 9, 10, 13, 15, 16, 21, 28, 29, 30, 31. Sep 3, 6, 7, 8, 10, 12, 14, 18, 19, 20, 21, 26, 27, 28, 29. Oct 1, 2.

Total No. of Visits *82*

The amount of Entry Fee.....£ *5: 0: 0*

Special Survey Fee ...£ *175: 19: 0*

Travelling Expenses, if any £ : :

Fees applied for,

8th Oct 1906

Received by me,

12/10/06

Certificate to be sent to

This Office

State whether the Vessel has been built under Special Survey

I am of opinion this Vessel should be Classed ** 100 A. 1*

With, or without Freeboard, as condition of Class

Steel Shelter Dk with freeboard.

Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

FRI. 12 OCT 1906

Character assigned

*100 A. 1
Shelter dk with fbd 5.5.6.2*

Lloyds' Arb O

*+ Lm 6 1006
F. D. E. L. H. G.
Ref. M. 1006*



© 2021

Lloyd's Register
Foundation