

W783-0016 C12

Steel S.S. "VICTORIEUX" ex "ALENTEJO". Rot. No. 11332.  
-----  
e-----

Rule Dimensions 400' x 52.5' x 27.25' to upper deck.  
x 35.0' to Shelter deck.

Scantling Nos. 79.75 & 31900.


Proportions :- Length = 11.4 depths to Shelter Deck.  
-----

This vessel was built by the Bremer Vulcan in 1911 and was  
ed with Germanischer Lloyd's.

It is now desired that the vessel shall be classed with  
Society.

The vessel had received very heavy fire damage, necessitating  
reconstruction above the bilges. Plans showing the repairs  
affected were forwarded by the repairers in August last, and  
vessel was built on the Longitudinal system of framing, plans  
vessel as built were obtained from the designer, Mr. Isherwood.  
The scantlings and arrangements as indicated on the plans  
examined and compared with the rule requirements and with the  
ce of the Committee for vessels framed on the longitudinal  
and were approved; subject to amendments being carried out,  
antlings as shewn on plans verified by the Surveyors, the  
s carried out to their satisfaction; and for the class 100 A.1.  
er Dk. with freeboard".

Reports have now been received from the Rotterdam Surveyors  
particulars of scantlings etc. and these appear to be in  
ance with approved plans. The Surveyors state that the  
ements of section 48 of the rules, for vessels not built  
survey have been complied with and all new work and repairs  
out in accordance with approved plans.



P. T. O.

© 2020  
Lloyd's Register  
Foundation

It is submitted the vessel might be classed 100 A.1. (steel) Shelter Dk. with freeboard", as recommended. The Summer freeboard 1'-2" from centre of disc to top of statutory deck line at Shelter Dk., now marked on the vessel's sides, to be inserted in classification certificate, and recorded in the Register Book, further, the remaining freeboards, as shown on the accompanying classification form to be inserted in the certificate of classification 100 A.1. (Stl.) "Shelter Dk. with freeboard".

1 Dk. (Stl.) & Shelter Dk. (Stl.-ws) and 3rd.Dk.(Stl.) in forehold, & Webframes. Longitudinal framing.

Cell DB 351' 1263t. FPT 20t. APT 44t.

FK. 6 BH. to Shelter Dk. Cem. Lloyd's A.& C.P.

Date of build 1911.

S.S.Rot.No.2-20.

7.20 Rot.

13. 8. 20.

It is concluded the <sup>workmanship</sup> of both old and new work satisfactory, but the Surveyors should be requested to state if so.

-----



© 2020

Lloyd's Register  
Foundation

W783-0006 (2/2)