

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) **G.Y.C.B.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
163,957.	St. Achilleus.	63/1934 Hull.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam S/Screw.	Beverley.	1934	Cook Walton & Gemmell Limited, Beverley.

Number of Decks .. <b>One &amp; Raised Quarter Deck</b>	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post .. .. .	Feet.	Tenths.
Number of Masts .. <b>Two</b>	Length at quarter of depth from top of weather deck at side amidships to bottom of keel .. .. .	164	4.
Rigged .. .. <b>Ketch</b>	Main breadth to outside of plank .. .. .	27	3.5
Stern .. .. <b>Cruiser</b>	Depth in hold from tonnage deck to ceiling at midships .. .	14	4.
Build .. .. <b>Clincher</b>	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards .. .		
Galleries .. .. <b>None</b>	Depth from top of beam amidships to top of keel .. .		
Head .. .. <b>Straight Stem</b>	Depth from top of deck at side amidships to bottom of keel ..		
Framework and description of vessel .. .. <b>Steel Trawler</b>	Round of beam .. .. .		7.5
Number of Bulkheads .. <b>Five</b>	Length of engine room, if any .. .. .	36	8.5
Number of water ballast tanks, and their capacity in tons .. <b>None</b>			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ----- Tons. Ditto per inch immersion at same depth ----- Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Reciprocating Steam Triple Expansion Direct Acting Inverted Cylinder.	British	1934	Charles D. Holmes & Co. Ltd., Hull.	Three	14 1/2"	27"	N. H. P. 154 I. H. P. 850
One	Cylindrical Multitubular Boilers.	British	1934	Charles D. Holmes & Co., Ltd., Hull.	Four	25"	41"	12 Knots.
	Number .. <b>Four</b>							
	Iron or Steel .. <b>Steel</b>							
	Loaded Pressure .. <b>215 lbs #</b>							

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck .. .. .	424.17	On account of space required for propelling power	230.79
Space or spaces between Decks .. .		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk .. .. .		These spaces are the following, viz. :-	44.75
Forecastle .. <b>Side Houses under</b> .. .	2.68	<b>Below Deck forward</b>	
Bridge space .. .. .		<b>Below Deck Aft.</b>	
Peep or Break .. .. .	22.19	(Number of Seamen or Apprentices for whom accommodation is certified.... <b>21</b> .....)	
Side Houses .. .. .	17.63	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Deck Houses .. .. .		<b>Masters Accommodation 7.52</b>	20.01
Chart House .. .. .		<b>Chart Space 1.58</b>	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 .. .	17.70	<b>Wireless Telegraphy Space 2.53</b>	
Excess of Hatchways .. .. .		<b>Boatswains Store 8.38</b>	
	484.07	Cubic Metres.	
Gross Tonnage .. .. .		1370.77	
Deductions, as per Contra .. .	295.55	836.41	
Register Tonnage .. .. .	188.82	534.36	295.55

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **115.58** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **19.19** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle L.29'.0 - 20.30 Tons.

Name of Master	Certificate of	Service Competency
No. of Owners		
Name, Residence, and Description of Managing Owner if there are more owners than one.		
Thomas Hamling and Company Limited St. Andrews Dock, Kingston-upon-Hull Sixty-four (64) Shares.	Thomas Boyd of "Dunvegan" Heads Lane, Hessle, E. Yorks.	- Manager -
Dated <b>3rd December 1934.</b>		



W79-0140

W79-0142

Mr. Soden



© 2020

Lloyd's Register  
Foundation