

(LLOYDS REGISTER.)

G. R. 130  
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) J. V. W. F.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
142767	War Anchusa	11 Jan 1919 London

No., Date, and Port of Previous Registry (if any) ✓

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	Greenock	1919	Card & Co. Ltd. Greenock

Number of Decks	Number of Masts	Rigged	Stern	Build	Galleries	Head	Framework and description of vessel	Number of Bulkheads	Number of water ballast tanks and their capacity in tons	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post		Length at quarter of depth from top of weather deck at side amidships to bottom of keel		Main breadth to outside of plank		Depth in hold from tonnage deck to ceiling at midships		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		Depth from top of beam amidships to top of keel		Depth from top of deck at side amidships to bottom of keel		Round of beam		Length of engine room, if any	
										Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.	Feet.	Tenths.
One	One for wireless	none	elliptical	Clunches	none	none	Steel Cargo	Seven	Seven 1395 tons	400	1	400	-	52	3	28	5	-	-	32	0.8	31	2.6	1	0.8	47	5

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel... 10620 Tons. Ditto per inch immersion at same depth... 41.5 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
one	Inverted direct acting triple expansion	British	1919	Card & Co. Ltd.	Three	27"	48"	517
one	Cylindrical Boilers	British	1919	Greenock	44"	73"	-	3000 11 1/2 knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck	...	4804	44	On account of space required for propelling power	1690
Space or spaces between Decks	...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	49
Turret or Trunk	...			These spaces are the following, viz.:	
Forecastle (houses under)	...	6	44	In poop and in deck houses	250
Bridge space	do	14	66	and side houses on bridge.	04
Poop or Break	...	16.2	31		
Side Houses	...	35	01		
Deck Houses	...	100	71		
Chart House	...	7	08		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	...	68	33	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:	
Excess of Hatchways	...	83	80	Cubic Metres	
Gross Tonnage	...	5282	78	Master's accommodation 76	76
Deductions, as per Contra	...	2093	45	Boatswain's Stores 28.59	28.59
Registered Tonnage	...	3189	03	Chart Space 7.08	7.08
				Wireless House 4.31	4.31
				Water ballast space 105.18	105.18
				Total	153.22

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 620.60 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 107.29 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

open fore-castle 37.7 feet long less side houses hatchways = 71.60 tons  
open bridge space 112.5 feet long = 447.93  
less house, engine & boiler casings, steam steering house hatchways = 97.25  
350.65 tons

Name of Master Certificate of { Service No. Competency No.

No. of Owners Name, Residence, and Description of Managing Owner if there are more owners than one. Manager

His Majesty represented by the Shipping Controller, London. Sixty four Shares  
Joseph Temperley & Co. 87, Bishopsgate, London, E.C. 2.

Dated 15th January 1919.

W 80-0172