

Lloyd's Register of Shipping,

Keizersgracht, 302-304

Binnengasthuisdijk 27XXX

LLOYD'S REGISTER
LONDON.

Amsterdam, 22nd May, 1916.

RECD MAY 26 1916

AN8D

VEENDAM DISTRICTS

Persons to be addressed to—
SURVEYORS.

The secretary

London.

Dear Sir,

With reference to Your letter of the 15th instant respecting
our first Entry report No 6965 on the S. S. "OTIS TETRAX" and with
regard to the position of the bulb angle frames 6 x 3 x .40", We
beg to inform You that these frames are fitted as under.

Frames Nos. 1 to 6	Angle bar 5 x 3 x .38"
" " 8 to 31	" " 5½ x 3 x .40 reversed frames on
" " 11, 14, 17, 20, 23, 26 & 29	" " 4 x 3 x .36"
" " 35 to 42	Bulbangle 6 x 3 x .40" reversed frames on
" " 34, 37 & 40	Angle bar 4 x 3 x .36
" " 43 to 53	Bulbangle 6½ x 3 x .44
" " 55 to 84	" " 6 x 3 x .40" reversed frames on
" " 58, 61, 64, 67, 70, 73, 76, 79 & 82	Angle bar 4 x 3 x .36"
" " 85 to 104	Bulbangle 6 x 3 x .40"
" " 106 to stem	Angle bar 5 x 3 x .40"

© 2021

Lloyd's Register
Foundation

W806 - 0006 ½

thickness of A, B & C strakes of the fore end are.

B .46" and C .46" which has been erroneously omitted on
part.

plan of the masts and an amended Midship section and profile
will be forwarded within a short time.

I am, Dear Sir

Your obedient Servant

J. H. L. Loe.



© 2021

Lloyd's Register
Foundation

W806-0006 $\frac{3}{2}$

MAY 26 1916

Also for Mr. S. A. Hill to note.

85
 265-16
 11

FROM, SPECIAL AGENT
IN CHARGE, FBI

.ers dne etot ent to exerts O & E, A to be
 ne bestimo Vlasovenerite need and holds "ob.
 ellyterq dne noljosa qinabim bebness na dne etasen ent 1
 .entj itrona a ninfier delawwot

© 2021 Lloyd's Register Foundation