

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) _____

Official Number.	Name of Ship.		No., Date, and Port of Registry.	
122805.	"Langland"		1/1906. Swansea.	
No., Date, and Port of Previous Registry (if any). <i>First Registry. New Vessel.</i>				
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British.	Steam Screw.	North Shields	1905.	Smiths Dock Company Ltd North Shields
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	120	Tenths. 8
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	120	-
Rigged ...	Ketch	Main breadth to outside of plank ...	22	1
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	12	.
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	13	33
Galleries ...	None	Depth from top of beam amidships to top of keel ...	13	47
Head ...	None	Round of beam ...	31	5
Framework and description of vessel ...	Steel	Length of engine room (if any) ...		5
Number of Bulkheads ...	Three			
Number of water ballast tanks, and their capacity in tons ...	None			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ...	380 tons.	Ditto per inch immersion at same depth ...	5 tons.
--	-----------	--	---------

PARTICULARS OF ENGINES (if any).

No. of Engines.	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One Set.	Engines. Triple Expansion direct acting inverted cylinders	British	1905	Mac. Coll & Pollock Ltd	Three 12 1/2"	24"	57 440 10 Knots.
	Boilers. Number..... One Iron or Steel Steel Pressure when loaded 180 lbs		1905	Sunderland	20" 34"		

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	218.77	On account of space required for propelling power	132.81
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	26.40
Space or spaces between Decks ...	8.10	These spaces are the following, viz.:—	
Deck ... Break ...			
Forecastle ...	3.57		
Round House ...			
Other closed-in spaces, if any, as follows:—			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894, if required.	9.93	Deductions under Section 79 of the Merchant Shipping Act, 1894, as follows:—	
		Boatswain's Store 3.50	
		Cubic Metres Master's berth 2.07	
		Chart House 3.57	9.14
Gross Tonnage ...	240.37		
Deductions, as per Contra ...	168.35		
Registered Tonnage ...	72.02	Total Deductions ...	168.35

Name of Master


Certificate of { Service No.
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

The Heron Steam Trawler Company Limited, having its principal place of business at South Dock Basin, Swansea, } sixty-four shares

Crawford Heron, of above address, Manager.

Dated 15th January 1906.

© 2020

Lloyd's Register

W 825 0116

W825-0116