

(LLOYD'S REGISTER.)

G.R. 130
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any)

K.R.M.H.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
148,275.	SOUTHBOROUGH.	28/1924 Cardiff.

No., Date, and Port of Previous Registry (if any).		Initial Registry.		
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Single Screw.	Thornaby-on-Tees.	1924	Richardson Duck & Co., Ltd. Thornaby-on-Tees.
Number of Decks	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	399	Feet.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	398	Tenths
Rigged	Schooner	Main breadth to outside of plank	53	0
Stern	Elliptic	Depth in hold from tonnage deck to ceiling at midships	24	9
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	---	---
Galleries	None	Depth from top of beam amidships to top of keel	28	5
Head	None	Depth from top of deck at side amidships to bottom of keel	27	6.5
Framework and description of vessel	Steel cargo	Round of beam	1	1
Number of Bulkheads	Six watertight	Length of engine room, if any	50	0
Number of water ballast tanks, and their capacity in tons	Seven 1439 tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel **9460** Tons. Ditto per inch immersion at same depth **41.57** Tons.

* PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Vertical triple compound Direct Acting Surface condensing	Engines.	Engines.	Engines.	Three			417
		&	&	&	25 1/2"			2000
	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	42"	48"	---	10 Knots
One	Description..... Cyl. Multr. Number..... 3 Iron or Steel..... Steel Loaded Pressure..... 180 lbs per sq. in.	British	1924	Blair & Co., Ltd., Stockton on Tees, 70"				

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		4205.61	On account of space required for propelling power		1453.30
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		189.24
House in Shelter Deck	23.00		These spaces are the following, viz.:-		
Forecastle	37.08		Forecastle Poop and Round Houses		
Poop	101.47				
Side Houses	168.78				
Deck Houses	5.62				
Chart House					
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894			Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Excess of Hatchways			Master's Accomn.	17.20	144.60
			Boatswains Store	45.42	
			Wireless Room	3.50	
			Chart Room	5.62	
			Fore Peak Tank	33.76	
Gross Tonnage	4541.56	12852.61	After Peak Tank	39.10	1787.14
Deductions, as per Contra	1787.14	5057.60			
Register Tonnage	2754.42	7795.01			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **687.81** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **138.05** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle length 35.4 - 58.20 tons
 Open Space in Shelter Deck Part I length 341.0' - 1128.74 tons.
 " II " 5.0" - 17.53 "

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	Thomas Bernard Humphries same address, Manager.
The Hazelwood Shipping Company Limited } Baltic House, Cardiff.	Sixty-four (64) Shares.

Dated 30th September, 1924.

