

CONSTRUCTION SECTION.  
DIMENSIONS.

LENGTH OVERALL	223' 0"
" BETWEEN PERPENDICULARS	200' 0"
BEAM OVER PLANK	41' 8"
DEPTH OF HOLD	19' 10"

FALSE STEM W.O. SIDED 18" AND MOULDED 8"  
STEM: W.O. SIDED 18" AND MOULDED 20" IN ONE PIECE  
BACKED BY APRON 22"x24" FULL LENGTH IN ONE PIECE  
CONNECTED TO KEEL BY OAK KNEE ARMS ABOUT  
8 FEET AND 4 1/2 FEET AND SIDED 18" FASTENED WITH  
1 3/8" BOLTS.

DEADWOOD AFT SIDE SAME AS KEEL AND MOULD SUFFICIENT TO TAKE ENDS OF CEILING.

FRAMES DOUBLE SPACED 30" CENTERS LAPS  
TO BE NOT LESS THAN 48" SECTIONS OF THE

PLANKSHEER 6"x15" BUTTED AND WELL BOLTED  
THROUGH BEAM AND CLAMP

CLAMPS 5\*12" FULL DEPTH OF BULWARK HEIGHT  
WELL EDGE BOLTED TOGETHER WITH AIRSTRAP

SHELF 6"x4" EDGE BOLTED TO CLAMP.  
RUDDER STOCK W.O. 20" DIA. 4 BRASS STRAPS

DESIGNED BY COX & STEVENS



Lloyd's Register

*M. Plimley*

*Private*



RECEIVED

*Frederick Jackson*



© 2021

World's Register  
Foundation

W836-0154