

Horlock's Bituminous Cement proposed for use in S/S. "Hull Lader."

This vessel has been built by Messrs Cochrane & Sons for Mr. F. W. Horlock and the Surveyors report that the bottom inside is coated with Horlock's Bitumastic Cement a sample of which they have forwarded to this office.

The composition of this cement is as follows: -

Pitch	250 lbs.
Tar	6 gallons = about 60 lbs.
Cement	360 lbs.
Linie	56 "
Resin	14 "

From the sample forwarded this cement appears to be adhering satisfactorily to the plate and it is submitted it may be approved subject to a biennial examination as required by the Rules.

12/11
5.10.11

B.

E. L. L.
10.2.11



© 2020

Lloyd's Register
W856-0178
Foundation