

G.R. 130.

40350

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

18 FEB 1938

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) GDGX

Official Number.	Name of Ship.	No., Date, and Port of Registry.			
165697	TASSO	4/1938 Hull			
No., Date, and Port of previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Screw	Walker on Tyne	1938	Swan, Hunter & Wigham Richardson Limited, Walker on Tyne.	
Number of Decks	.. One & Shelter	Length from fore part of stem, to the aft side of the head of the stern post		Feet. 283	Tenths. 9
Number of Masts Two	Main breadth to outside of plank		40	2
Rigged Not	Depth in hold from tonnage deck to ceiling amidships		15	8.5
Stem Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards.. .. .			
Stern Cruiser	Depth from top of deck at side amidships to bottom of keel ..		25	4.4
Build Clencher	Round of beam			8.3
Framework and description of vessel	Steel Cargo Vessel	Length of engine room, if any		42	7.5
Number of Bulkheads	Watertight - Five				

Particulars of propelling Engines, etc., (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Estimated Speed of Ship.
One	Triple Expansion Direct Acting Vertical with Bauer Wach System of L.P. Turbine	Engines.	Engines.	Engines.	Three			335
		and	and	and	19 1/2"	36"	One	2200
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	33"			13 3/4
One	Hor. Cyl. Mult.	British	1938	Swan, Hunter & Wigham Richardson Ltd., Walker on Tyne.	54"			Knots
	Number Two							
	Iron or Steel Steel							
	Loaded Pressure 210 lbs.							

Number of water ballast tanks, and their capacity in tons:— Seven = 412 Tons.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	1220.42	On account of space required for propelling power	638.33
Shelter Space or spaces between Decks (House in)	15.47	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	133.35
Turret or Trunk	24.52	These spaces are the following, viz.:—	
Forecastle (Lower)	64.39	Poop and Round Houses.	
Bridge space	179.62	(Number of seamen or apprentices for whom accommodation is certified.....32.....).	
Poop or Break	79.06	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses	2.81	Masters Accommodation	8.66
Deck Houses		Chart Space	4.70
Chart House		W/T. Space	2.55
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Bosn's Store	15.86
Excess of Hatchways		W.B. Spaces	15.27
		Total	47.04
Gross Tonnage	1586.29	Cubic Metres.	4489.20
Deductions, as per contra	818.72		2316.98
Register Tonnage	767.57		2172.22

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 285.70 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 84.16 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Shelter 'Tween Deck I	L 42.8'	=	100.42 tons.
II	L 67.4'	=	177.73 "
III	L 47.2'	=	78.56 "
IV	L 67.45'	=	191.83 "
Tonnage Well	L 4.45'	=	11.15 "

Name of Master	Certificate of	Service No.	Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Ellerman's Wilson Line Limited, Commercial Road, Kingston-upon-Hull.	Manager: John Wyrill Bayley of same address.		
Sixty Four (64) Shares.			
Dated this the Eighth day of February 1938.			

Manager: John Wyrill Bayley of same address.

Lloyd's Register Foundation

W87-0103

Mr. Soder



© 2019
Lloyd's Register
Foundation