

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosure.

7th May, 1937.

Dear Sirs,

E.

I duly received your letter of the 30th ultimo, with enclosures advised therein respecting shafting proposed for Messrs. Swan, Hunter & Wigham Richardson's Yard Nos. 1580 and 1582, and I have to inform you that with triple expansion steam reciprocating engines for ocean going service, combined with an exhaust turbine on the Bauer Wach system, developing a combined equivalent IHP of 2200 at 115 revolutions per minute of the propeller, having diameter of cylinders $19\frac{1}{2}$ ", 33" and 54", stroke 36", and working pressure 210 lb. per sq. inch, the following size of thrust shaft will be approved, viz:- 290 mm.

The plan showing details of the thrust shaft and cone coupling will also be approved, and two copies of this plan are returned herewith.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,
NEWCASTLE-ON-TYNE.



© 2018 Secretary.

Lloyd's Register
Foundation

W87-0132