

Steel Screw Steamer No.27 proposed to be built by Messrs.
The Forth Shipbuilding Co. with a view to class 100A1.

Rule Dimensions: 305 x 42.5 x 23.75.

Scantling Numbers: 66.25 & 20206.

Proportions: Length = 12.84 depths to upper deck
9.84 " " bridge deck.

It is proposed to build this vessel as a duplicate
of the same Builders' No.26, plans of which were approved on
the 28th September 1916.

(For omission of bulkhead see separate endorsement)

This vessel was originally intended to be classed
with the British Corporation, but the Builders now desire her
to be classed in this Society's Register Book.

In the case of the Builders' No. 26 it was found
necessary, in order to make the scantlings equivalent to the
Rule requirements, to double one strake of bottom plating and
the sheerstrakes, to fit additional reversed frames and to
effect certain minor alterations to the scantlings and arrange-
ments, the material being ordered and partly delivered.

In the present case it was intended to build the
vessel in accordance with the Rule requirements but the Builders
now state that with this vessel they are in the same position
with regard to the delivery of the material as in the case of
their No. 26.

It is submitted that provided the vessel be built in
accordance with the plans of the sister vessel referred to

COMPLIANCE

the vessel will be worthy to be classed 100A1.

bbp
8.11.16.



© 2020

Lloyd's Register
Foundation