

Received by Chief Ship Surveyor 16/10/11.

Received from Chief Ship Surveyor _____

VESSEL'S NAME Stl. 455 "Galway Castle" Rpt. Bel. No. 6998.

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Transverse No. 89.79 Depth "d" 13.2

Framing: Table No. 3 page Description Channel frames as approved.

Longitudinal No. 40585

Proportions Length = 10.70
Depth = _____

Bridge Deck Sheerstrake as per rule.

Flat plate keel 12" less in thickness than required but compensated for by increased breadth & by the fitting of an outside doubling 10" x 2".

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed **✦ 100A1 ("Steel")** as recommended.

✦ 100A1 ("Steel")

2 Dks (Stl. v Leaks & 2nd D^K W.S.) + 3rd D^K (Stl.) in No. 1-3-4+5 holds. "Well deck"

WB = cell DB w 128' v E + B 87' f 171' 1204 t. F.P.T. 70 t. A.P.T. 80 t.

FK + BK 2" 8BH. Cem. Lloyds A.V.C.P. P + B 272' F 71'

W896-0023



© RLL 20
16/10/11
Lloyd's Register
Foundation