

215

Steel Screw Steamer No. 451 proposed to be built by Messrs.
Cochrane & Sons with a view to class 100A1, "Steam Trawler".

Rule Dimensions ; 164.8 x 26 x 15.46

Equipment Numbers - 8714.

This vessel is of a size somewhat beyond that
provided for by Table 22 of the Rules for Steam Trawlers,
and the equipment obtained by an extension of Table 22 of the
Rules for steam trawlers/and the equipment proposed by the Builders
are as follows;-

As required by an extension
of Table 22.

As proposed.

power anchor 9cwts. 1 qr. 14 lbs stkless

1 bower anchor 9 cwts. 1 qr

" " 9 " 1 " 14 " "

1 " " 9 " 1 qr.

Age " 4 " ex stock

Kedge " 3 " 3 qrs
ex stock

0 fathoms 1 3/16" chain cable

150 fathoms 1 3/16" chain cable

0 " 7" hawser (or 2 1/2" steel wire)

60 fms. 7" hawser (or 2 1/2" stl wire)

0 " 5 1/2" warp (or 2" steel wire)

60 " 5" warp (or 1 3/8" stl wire)

It will be observed that the weights of the anchors
proposed are slightly less than those required by an extension
of Table 22 for Steam Trawlers, and the size of the warps
proposed is also less than that required.

It is submitted that provided the equipment be supplied
in accordance with that required by an extension of Table 22
for Steam Trawlers as above, the same might be approved
for the figure 1 as in previous similar cases.

mission TUES. 15 DEC 1908

Approved

Dr 12.12.08
Ans 15

CR
15.12.08.
© 2020
Lloyd's Register
Foundation
W918-0028