

NET

Owners' Address

(if not already recorded in Appendix to Register Book).

Surveyed. Afloat or in Dry Dock?

Both

Name of Dock

Shields & Co

Destined Voyage

Location (which
Register Book &

4m. 113.

WRECK BOX

No.

8 Bilton

Received by Chief Ship Surveyor

19. 2. 14

Received from Chief Ship Surveyor

VESSEL'S NAME

M. S. N. Celtic

Rpt.

NWC

No.

65581

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Nature of Survey

Condition & Alterations

The Newcastle Surveyors report that they have examined this vessel in drydock, and the bottom has been cleaned and coated, and the following alterations carried out:—

The steel top, wash plate, trunk and bulkheads of fish well have been removed; a new W.T. bulkhead has been fitted on frame 41 extending to deck; this bulkhead has been properly stiffened and fitted between double frames (1 new) and new double deck bars; a watertight coal trimming trunk has been built from new W.T. bulkhead on frame 41 to bunker and stockhold (coal bulkhead only) on frame 30; on frame 30 this trunkway is fitted with a W.T. door worked from above water line; the long hatchway over fish well removed; all beams carried across opening and new small hatchways fitted as shewn on attached sketch; all iron work in bunkers and fish hold laid bare cleaned and coated; new lining fitted in all these spaces; wooddeck over same part renewed; steel deck plating fitted between small hatchways, and minor repairs effected.

A trawl winch and other gear for trawling has also been supplied.

It is submitted the vessel appears worthy to be classed 100A1 "Steam Trawler" with record of survey 2,14 as recommended.

Alter class to - 100 A.1
"Steam Trawler" Shl.
2. 14 Shl.

W938-0097

of survey 2.14 Shl

Signed) as
verified

this purpose

tail

new

bulk

with a

RT Sta

e 30

in line

ams

on

Clear

T.M. of Wood
(on Felt.)
on, Month

is, &c.

ow ascertained

wedges ren

letter

o. of

te if now ra

board)

length

Warps

Running Rigg

Register Book
ass and to

ely

2