

s.s. "GAASTERLAND". No.22325 in Register Book.

Messrs. Rotterdamsche Droogdok Maats Boiler Nos.457/8.

IT IS SUBMITTED the plan of boilers merits approval for a working pressure of 180 lb. per sq. inch, provided the diameter of the rivet holes in the manhole compensating plate be not less than 1.5/32"; a loose washer be fitted to the upper longitudinal stay at the lower back end plate and nuts be fitted to the lower longitudinal stays to the lower back end plate, as indicated on the plan and the boilers be constructed under the usual conditions of survey and testing.

Return plan.
Retain copy.

L 6/7/27



L.R.H.

© 5.7.27.

Lloyd's Register
Foundation

W 96 - 00 43