

16 MAY 1919

Received by Chief Ship Surveyor .....

Received from Chief Ship Surveyor .....

VESSEL'S NAME Steel S.S. "CYRANO". Rpt. Fal. No 5844**The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.**

(The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement.—Extract from Sub-Committee's Report, 24/5/32.)

Nature of Survey Re-conditioning & Part SS No 3 due 8.17

The 1st. s.s. No. 3 became due 8.17.

The Falmouth Surveyors report the vessel examined in dry dock and the following repairs for reconditioning carried out:- stem removed and faired, several shell plates repaired, bunker hatches refitted, deck repaired and minor repairs.

The s.s. No. 3 has also been partly held.

Further repairs are required to shell and bulwark plating.

It is stated the special survey and repairs will be completed at Grimsby.

It is submitted action be deferred and "Examined 4.19" recorded in red ink in the Register Book.

   
15. 5. 19.

The Grimsby Surveyors should be informed that to complete the survey the bunkers require to be examined and all ceiling in same lifted, the watertight door to be examined, plating in way of sidelights (if any) to be examined and the shell plating to be drilled if considered necessary. Repairs to be effected to a number of shell and bulwark plates as detailed in report.

W 466-0075



© 2020

Lloyd's Register  
Foundation