

No. 18989.

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office 14 JAN 1936

13/11/1936 When handed in at Local Office 13/11/1936 Port of *Leith*
 Date, First Survey 31/10/35 Last Survey 8/11/1936
 Survey held at *Burntisland*
 Reg. Book. *S/S "WOODBURY"*
 0660 on the *S/S "WOODBURY"*
 Built at *Burntisland* By whom built *Burntisland S.B.C.L.* Yard No. 185 When built 1936
 Owners *Alexander Shipping Co. Ltd. (Copper Alexander & Co.)* Port belonging to *London*
 Electric Light Installation fitted by *Burntisland S.B.C.L.* Contract No. 188 When fitted 1936
 The Vessel fitted for carrying Petroleum in bulk *No.*

System of Distribution *Two Wire* ✓ volts, Power 110 ✓ volts.
 Pressure of supply for Lighting 110 ✓ volts, Heating ✓
 Direct or Alternating Current, Lighting *Direct* ✓ Power *Direct* ✓
 If alternating current system, state frequency of periods per second ✓
 Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off *Yes* ✓
 Generators, do they comply with the requirements regarding rating *Yes* ✓, are they compound wound *Yes* ✓
 If not compound wound state distance between each generator ✓
 Are they over compounded 5 per cent. *Yes* ✓, is an adjustable regulating resistance fitted in
 Where more than one generator is fitted are they arranged to run in parallel ✓
 Are all terminals accessible, clearly marked, and furnished with sockets *Yes* ✓, are they so spaced or shielded that they cannot be accidentally earthed, ✓
 Are the lubricating arrangements of the generators as per Rule *Yes* ✓
 Position of Generators *Starboard side engine room* ✓, are they clear of all inflammable material *Yes* ✓
 Is the ventilation in way of the generators satisfactory *Yes* ✓
 If situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators *4 ft horizontally* ✓
 Are the generators protected from mechanical injury and damage from water, steam or oil *Yes* ✓
 Are their axes of rotation fore and aft *Yes* ✓
 Earthing, are the bedplates and frames of the generating plant efficiently earthed *Bolted direct to earth* ✓ are the prime movers and
 their respective generators in metallic contact *Yes* ✓
 Main Switch Boards, where placed *Starboard side engine room* ✓
 If the generators and main switchboard are not placed in the same compartment, is each generator provided with
 a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓
 Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes *Yes* ✓
 are they protected from mechanical injury and damage from water, steam or oil *Yes* ✓, if situated near unprotected
 woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards ✓ and
 are they constructed wholly of durable, non-ignitable non-absorbent materials *Sindango Panel* ✓, is all insulation of high dielectric strength and of
 permanently high insulation resistance *Yes* ✓, if semi-insulating material is used, are all conducting parts insulated from the slab
 with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework ✓
 and is the frame effectively earthed *Bolted direct to earth* ✓ Are the fittings as per Rule regarding: — spacing or shielding of live parts
 accessibility of all parts *Yes* ✓, absence of fuses on back of board *Yes* ✓, proportion of omnibus
 bars *Yes* ✓, individual fuses to voltmeter, pilot or earth lamp *Yes* ✓, connections of switches *Yes* ✓
 Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches *one 100 Amp:*
D.P. main switch & D.P. main fuses & 30 Amp: S.P. switch & D.P. fuses for outgoing
circuits
 Instruments on main switchboard *one* ammeters *one* voltmeters ✓ synchronising device for paralleling purposes.
 Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system *Earth lamps* ✓
 Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules *Yes* ✓
 Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule *Yes* ✓

BY AN INTERNAL
ON ENGINE.

Flash Point of Fuel.

HOW PROTECTED.

C & WA

C & WA

W.A.

W.A.

W.A.

C.

C.

PROTECTED.

S.W.A.

S.W.A.



© 2020

Lloyd's Register
W98-0158

Cables: Single, twin, ~~conductor or multi-core~~ are the cables insulated and protected as per Tables IV or V of the Rules *Yes*

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *3 Volts* *✓*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *Yes*

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *✓*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*

Support and Protection of Cables, state how the cables are supported and protected *Metal clips secured with screws.*

Machinery spaces & damp situations L.C. & W.A. Accom; L.C. Other places W.A.

If cables are run in wood casings, are the casings and caps secured by screws *✓*, are the cap screws of brass *✓*, are the cables run in separate grooves *✓*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *Yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *✓*

Joints in Cables, state if any, and how made, insulated, and protected *Standard junction boxes.*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made *Lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *Switchboard frame & Dynamo*
not bolted direct to earth. Brass bonding clips for earthing metallic sheathing
of all cables, are their connections made as per Rule *Yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *Yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *✓*

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes*
are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*
has each navigation lamp an automatic indicator as per Rule *Yes*

Secondary Batteries, are they constructed and fitted as per Rule *✓*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*
are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *✓*
are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *✓*
✓, how are the cables led *✓*
where are the controlling switches situated *✓*

Searchlight Lamps, No. of *✓*, whether fixed or portable *✓*, are their fittings as per Rule *✓*

Arc Lamps, other than searchlight lamps, No. of *✓*, are their live parts insulated from the frame or case *✓*, are their fittings as per Rule *✓*

Motors, are their working parts readily accessible *Yes*, are the coils self-contained and readily removable for replacement *Yes*
are the brushes, brush holders, terminals and lubricating arrangements as per Rule *Yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *Yes*
are they protected from mechanical injury and damage from water, steam or oil *enclosed* are their axes of rotation fore and aft *Yes*
if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *enclosed*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *✓* and *✓*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *Yes*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *✓*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *✓*
If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *✓*

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN ...	1	10	110	914	350	Steam Engine			
AUXILIARY ...									
EMERGENCY ...									
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR ...	one	.0750	19	.072	78.2	97	48	Rubber	L.C. & W.A.
EQUALISER CONNECTIONS ...									
AUXILIARY GENERATOR ...									
EMERGENCY GENERATOR ...									
ROTARY TRANSFORMER } MOTOR GENERATOR ...									
ENGINE ROOM ...	one	.0070	7	.036	17	22	56	Rubber	L.C. & W.A.
BOILER ROOM ...									
AUXILIARY SWITCHBOARDS ...									
Navigation	one	.0070	7	.036	3.5	22	360	Rubber	S.W.A.
Accommodation Saloon	one	.0070	7	.036	9	22	320	Rubber	
Engineers	one	.0070	7	.036	9.5	22	80	Rubber	
Cargo & Blast	one	.0100	7	.044	16.2	26	80	Rubber	
WIRELESS ...	one	.0070	7	.036	15	22	112	Rubber	S.W.A.
SEARCHLIGHT ...									
MASTHEAD LIGHT ...	one	.0020	3	.029	.36	7.8	480	Rubber	S.W.A.
SIDE LIGHTS ...	one	.0020	3	.029	.36	7.8	82	Rubber	L.C.
COMPASS LIGHTS ...	one	.0020	3	.029	.36	7.8	19	Rubber	L.C.
POOP LIGHTS ...									
CARGO LIGHTS ...									
ARC LAMPS ...									
HEATERS ...									

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...	one	one	.0030	3	.036	5	12	64	Rubber	L.C. & S.W.A.
CIRC. FRESH WATER PUMPS ...	one	one	.0030	3	.036	6	12	20	Rubber	L.C. & S.W.A.
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR ...										
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP ...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR ...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...										
VENTILATING FANS ...										



© 2020

Lloyd's Register Foundation

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

FOR THE BURNTISLAND SHIPBUILDING COMPANY LTD.

W. J. D. G. R. MANAGING DIRECTOR

Electrical Engineers.

Date 10/1/36

COMPASSES.

Distance between electric generators or motors and standard compass 115'

Distance between electric generators or motors and steering compass 116'

The nearest cables to the compasses are as follows:—

A cable carrying 36 Ampères 7" feet from standard compass 7" feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be Nil degrees on Any course in the case of the standard compass, and Nil degrees on Any course in the case of the steering compass.

FOR THE BURNTISLAND SHIPBUILDING COMPANY LTD.

W. J. D. G. R. MANAGING DIRECTOR Builder's Signature.

Date 10/1/36

Is this installation a duplicate of a previous case No If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c. This installation has been

efficiently fitted on board in accordance with the rules
The materials & workmanship are sound & good & the installation
was found satisfactory under full load & working conditions

Noted
21/1/36

Total Capacity of Generators 10 Kilowatts.

The amount of Fee ... £ 10 : 0 : 0 When applied for, 13-1-1936

Travelling Expenses (if any) £ : ✓ : 4-2-1936 5/2 When received,

Chas R. Rouchieffe
Surveyor to Lloyd's Register of Shipping.

Committee's Minute FRI. 24 JAN 1936

Assigned

see J. E. Machy Report.