

MESSRS. S.P. AUSTIN & SON'S S.S. NO. 344.  
THE N.E. MARINE ENG. CO'S CONTRACT NO. 2885.

PARTICULARS OF SHAFTING ETC.

Type of Machinery.	Triple Expansion.
Cylinder Bores.	14½" - 41" - 24".
Stroke.	30"
Working Pressure.	220 lbs. per square inch.
Propeller dia.	11'-9" ( <del>ass</del> )
Tunnel Shaft dia.	8¾"
Crank " "	8¾"
" " " in web.	9¼"
" pin dia.	8¾"
Thickness of web. H.P.	5⅜"
M.P.	5½" aft.
L.P.	5⅜"
Thickness round shaft eye.	4⅝"
" " pin "	4⅜"
Dia. of coupling.	1'-6"
Thickness of coupling.	2¼"
Bolts number & dia. screw	6 - 2¼". 2" - 6 T.P.I.
P.C.D.	1'-2"
Dia. of thrust shaft in way of collar.	8¾"
Dia. of tail shaft under liner.	9¼"
Continuous liner thick.	⅝"
Liner between bearings thick.	9/16"



© 2020

Lloyd's Register  
Foundation

W983-0299