

Messrs.Scheeps "Gideon" J.Koster Hzn. Yard No.161/2.

Pumping Arrangement.

IT IS SUBMITTED the Surveyors be informed it is noted from their letter of the 31st ultimo that the capacity of the main engine driven bilge pump is 10 tons per hour and not 80 litres per minute as previously stated.

In the circumstances, the proposed arrangement of one main engine bilge pump and one independent bilge pump will be accepted in this instance, but in future cases where this arrangement is adopted, the capacity of either of the pumps should not be less than $\frac{2}{3}$ that of the Rule capacity and the combined capacity of the two pumps not less than twice the Rule capacity.

Lob/4

[Handwritten signature]

[Handwritten initials]

[Handwritten signature]



4.4.38. 2019

Lloyd's Register
Foundation

W987-0211