

**(LLOYD'S REGISTER.)**  
**VESSELS OF 100 TONS AND UPWARDS.**

G.R. 130.  
Lloyd's Register.

*These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.*  
 Signal Letters (if any) L.B.C.N.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
149,978.	Westbury.	12 in 1928 London.

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Burntisland	1927	The Burntisland Shipbuilding Company Limited, Burntisland.

Number of Decks	One & Shelter	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ... ..	Feet.	Tenths.
Number of Masts	Two		405	----
Rigged ... ..	Fore & Aft.	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... ..	402	17
Stern ... ..	Elliptical		54	3
Build ... ..	Clencher	Main breadth to outside of plating ... ..	25	3
Galleries ... ..	None	Depth in hold from tonnage deck to ceiling at midships ...	--	--
Head ... ..	None	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ... ..	28	9.1
Framework and description of vessel ... ..	Steel Cargo	Depth from top of beam amidships to top of keel ... ..	28	0.4
Number of Bulkheads	Six W.T. & One Non W.T.	Round of beam ... ..	1	0.8
Number of water ballast tanks, and their capacity in tons	Seven - 2168 Tons	Length of engine room, if any ... ..	46	6

**PARTICULARS OF DISPLACEMENT.**

Total to quarter the depth from weather deck at side amidships to bottom of keel ... .. } **10248** Tons.      Ditto per inch immersion at same depth ... .. } **43.02** Tons.

**PARTICULARS OF PROPELLING ENGINES, &c. (if any).**

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B.H.P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Inverted direct acting Triple expansion condensing	Engines. British	Engines. 1928	David Rowan & Co., Ltd., Glasgow.	Three	48"		493
One	Horizontal cylindrical multitubular	Boilers. British	Boilers. 1928		44"			1850
	Number Three				73"			10 Knots
	Iron or Steel Steel							
	Loaded Pressure 180 lbs.							

**PARTICULARS OF TONNAGE.**

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ... ..		4453.58	On account of space required for propelling power		1507.78
Shelter Deck Space		9.43	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		177.62
Turret or Trunk ... ..	House in	25.47	These spaces are the following, viz.:-		
Forecastle ... ..			(Number of seamen or apprentices for whom accommodation is certified) 48		
Bridge space ... ..			Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Poop or Break Round		91.47	Masters Accommodation 11.60		} 105.65
Side Houses ... ..		126.68	Wireless Room 3.31		
Deck Houses ... ..			Chart Space 3.14		
Chart House ... ..		3.14	Boatswain's Stores (Limited) 47.12		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ... ..			Water Ballast Spaces 40.48		
Excess of Hatchways ... ..		2.24	After Peak Total ... ..		1791.05
Gross Tonnage ... ..		4711.80	Cubic Metres		
Deductions, as per Contra ... ..		1791.05	13334.39		
Register Tonnage ... ..		2920.75	5068.67		
			8265.72		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 665.02 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 105.81 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Shelter Deck Space Part I	L. 350.3	-	1175.39
" " " " II	L. 4.7	-	15.69

Name of Master \_\_\_\_\_ Certificate of { Service No. \_\_\_\_\_ Competency No. \_\_\_\_\_

No. of Owners \_\_\_\_\_ Name, Residence, and Description of Managing Owner if there are more owners than one.

Alexander Shipping Company Limited  
 4, St. Mary Axe.  
 London, E.C. 3.  
 Shares - Sixty-four.  
 Dated 9th January, 1928.

Charles Edward Alexander of same address, Manager.



W 99-0019