

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs.

Yard No.

Engineers: Messrs.

Engine No.

Owners: Messrs.

L.C.T. Mk. 3. Conversion for
The Neptune Shipping & Trading Co. Ltd.
amended

It is submitted that the plan of

Pumping ~~arrangement~~

Flooding and Draining Arrangement
merits approval, provided the arrangements be as
shown and amended on the plan and the remaining
requirements of Sections 20 and 34 of the Rules (1945-6)

be complied with so far as they are applicable.

It is noted that the duct keel is extended forward to frame h° 2 & that it is proposed to drain the forward compartment into the duct keel.

This arrangement will, however, place the forward compartment into communication with the hold and, accordingly, it is strongly recommended that the duct keel be closed in way of the bulkhead and that provision be made for draining the forward portion of the duct keel as now indicated on the plan.

Return 1 plan.

The remaining copy has been
Retain ~~copy~~

*handed to Mr. Sellers to
E. 43-700076 A copy of the letter
should be forwarded.*

h 10/10

W 992-0177

Lloyd's Register
Foundation

*82.83
9/10/46*