

mv. "MILDRED"

Electrical equipment examined and tested as required by the Rules.

Repairs due to war damage.

This vessel was sunk in war time and is now completely reconditioned.

All machinery was removed.

Crankshaft of main engine skinned, all bearings and bottom ends reinstalled. Lens driven, cylinder block cleaned and examined, aftwards hydraulically tested. Main engine fuel pumps renewed. Thrustshaft skinned, pads renewed. Bedding and alignment of shafting examined.

Aux engines and pumps, several parts renewed and completely overhauled.

Aldrup

Electrical Equipment

The electrical equipment of this vessel has been completely renewed in accordance with the Rules.

Generators and motors overhauled, dried and varnished.

Main switch board overhauled, current breakers, ampere and voltmeters renewed and an automatic voltage regulator installed for shaft dynamo 5 K.W.

Materials used are of good quality and workmanship good. The installation tested under working condition, current breaker operated at 150% of full load.

On completion resistance of all circuits was found good.

Spare parts are not in accordance with the Rules: for Mr Klein.

The following parts are missing at the moment. They have been ordered and are sent to the vessel upon arrival:

Spare propeller

" piston

Crank pin bearing

fuel pump parts for both auxiliary engines

Aldrup

RETAIN

RETAIN



© 2020

Lloyd's Register
Foundation