

## (LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) \_\_\_\_\_

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
146,285.		Lady Anstruther		11 in 1922 Glasgow.	
No., Date, and Port of Previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Screw	Dublin	1922	Dublin Shipbuilders Ltd. Dublin	
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...		Feet.	Tenths.
Number of Masts ...	Three	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...		167	4
Rigged ...	Schooner	Main breadth to outside of plank ...		26	6
Stern ...	Round	Depth in hold from tonnage deck to ceiling at midships ...		10	6
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...			
Galleries ...	None	Depth from top of beam amidships to top of keel ...			
Head ...	Straight	Depth from top of deck at side amidships to bottom of keel			
Framework and description of vessel ...	Steel Cargo vessel	Round of beam ...		35	5.5
Number of Bulkheads ...	Four	Length of engine room, if any ...			2
Number of water ballast tanks, and their capacity in tons ...	Three -- 200 tons.				

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 840 Tons. Ditto per inch immersion at same depth ... 8.5 Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Triple, Direct Acting, Vertical	Engines.	Engines.	Engines.	Three	27"		99
		and	and	and	14 1/2"			5801
No. of Shafts.	Particulars of Boilers.				24"			
One	Description: Horizl Return Tube	Boilers.	Boilers	Boilers.	40"			9 Knots.
	Number: One							
	Iron or Steel: Steel	British	1922	David Rowan & Co. Ltd. Glasgow.				
	Loaded Pressure: 180 lbs.							

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ...		362.93	On account of space required for propelling power		242.31
Space or spaces between Decks...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk ...		21.24	These spaces are the following, viz:—		41.39
Forecastle...		16.16	Forecastle, Bridge & Rd. House		
Bridge space ...		87.44	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Poop or Break ...		.05	Master 4.20		
Side Houses Expansion Trunk. ...		15.01	Chart Space 3.45		39.96
Deck Houses ...			Bosn's Store 10.00		
Chart House ...			Water Ballast 22.31		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		23.82	Cubic Metres		
Excess of Hatchways ...			Total ...		323.66
Gross Tonnage ...		526.65			
Deductions, as per Contra ...		323.66			
Registered Tonnage ...		202.99			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 138.46 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is \_\_\_\_\_ tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Boiler Casing 14' X 16' X 6.5' = 14.56 tons  
Engine " 14.4' X 16' X 6.5' = 14.98 "

Name of Master Colin Campbell

Certificate of { Service No. 103204  
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Nobel's Explosives Company Ltd., Nobel House, Buckingham Gate, London.  
Sixty-four shares.

Alexander Ross of Nobel House, Buckingham Gate, London, S.W.1.  
Manager.


Dated 17th February, 1922.

(830.) (871008) Wt. 23011/10 Gp. 144 2000 1-22 W &amp; S Ltd.

Diameter of Safety Valve

Pressure to which each is adjusted

Is Easing Gear fitted



© 2020

Lloyd's Register  
Foundation