

Wexford No 9

This is to Certify to whom it doth or may concern, that
the Smack Morris Castle of Wexford, whereof John Hull
is at present Master was repaired by me at Lawrence in
the County of Pembroke, and completed the first of
Oct^r 1834 (Viz) with great part of the Ceiling replaced
with new, and all defective Timbers were also replaced
with New Timbers, There were also several strakes of
British Oak plank shifted on the outside of the said
Vessel, and New Oak Bulge planks four inches thick on
each side and well Greenailed through to Two New
Strakes of thick stuff on the floor heads on inside of
the Vessel, and bolted to each other and well clinched
on the inside of the Vessel, and the whole of the planks
from the Keel to the Gunwall were very carefully inspected
and every plank with the least defect in it was replaced
with new, and the said Vessel was well and substantially
fastened with Butt Bolts and Greenails from Keel to
Gunwall which were of a sufficient size for a Vessel of
Eighty or Ninety Tons, and the whole of the workmanship
was executed in the best and most particular manner,
and the Vessel was well caulked from Keel to Hatchway
which repairs cost upwards of Seventy five pounds
and the said Vessel at the time of leaving my Ways was
tight, staunch, and strong, and well fitted to receive on
Board any Merchandise, goods or cargo, either Foreign or
Coastwise, and the s^d Vessel had a very fine Keelson rider fixed
by me in the year 1832 and other repairs which cost upwards of
£ 72, Given under my Hand the 2^d Oct^r 1834
Thosrd Canton

WEX1031-0010

Lloyd's Register
Foundation